



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II



BHAGYANAGAR GAS LIMITED
(A JOINT VENTURE OF HPCL & GAIL)

BID DOCUMENT FOR

**Annual Rate Contract for Inspection, Testing, and Refurbishment of CNG
Cascades at Vijayawada and Kakinada for a Period of Three Years**

**UNDER OPEN DOMESTIC
COMPETITIVE BIDDING**
e- tender

Bid Document No.: BGL/689/2025-26

VOLUME-II of II



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

CONTENTS

VOLUMEN II OF II

SECTION 7 -	Brief Scope of Work
SECTION 8 -	Specification of Work.
SECTION 9 -	Special Terms & Conditions
SECTION 10 -	Locations of Cylinder Cascades.
SECTION 11 -	Schedule of Rates / Price Schedule



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

SECTION – 7 BRIEF SCOPE OF WORK



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

SCOPE OF WORK

1. The bidder shall arrange for removal of CNG cascade from station / location of its installation.
2. All the tubing work necessary for removal of cascade from station is in bidder's scope. After removal of cascade, tubing necessary for operation of station is also in bidder's scope. Tubing and fittings required for the purpose will be provided by BGL. The bidder shall have to use same material at all the stations. Bidder has to obtain BGL authorization and Permit to Work (to isolate & remove cascade(s) from current location, arrange crane of appropriate capacity and LCV / Truck for unloading and transportation of the cascades at given CNG outlet as per the BGL Cascade replacement schedule. Hydra/Crane/Vehicle driver shall possess the Valid transport License (Heavy / Transport). Hydra shall have Valid Form NO 38. Safety latch shall be available on crane hook. Crane shall have valid Testing Certificate of Slings (Neoprene / Wire Rope). Crane shall have valid Testing Certificate of D-Shackles Crane shall have Wooden Wheel Stoppers (4 Nos). Every personal involved in unloading, transportation & cascade tubing work shall wear PPE's
i.e. Safety shoes, helmets, safety jackets. Load the cascade on the LCV / Truck and provide proper support to avoid any damage during transportation to the place of work, and unload safely at the place of work. Transportation of the cascade shall be carried out as per PESO guidelines. Venting of the gas from the cascade cylinders shall be carried out through PESO approved venting facility at a work place.
3. The cascades are installed in CNG stations at different locations. The bidder shall remove these cascades from the original locations. The necessary services required for lifting & installation viz crane, rigger gang etc will be in bidder's scope.
4. The hydra/crane/vehicle driver shall possess the valid statutory license.
5. In case of locations where removal of cascade by crane is not possible or arrangement of suitable crane is difficult, BGL may allow for removal of fencing made up of weld mesh structural steel along with restoration, grouting & associated civil works on case-to-case basis. In such cases removal & re-fitting to its original condition will in bidder's scope. All material, work force and other resources required for such work will be in bidder's scope. BGL will not make any arrangement in this regard. Delay in completion of work will lead to penalty as per the relevant clause.
6. The bidder shall carry out lifting and installation in daytime as per BGL schedule .BGL normally allows work on Saturday and Sunday. However, this will not deter BGL in requesting work in nighttime and in weekdays. The completion of work should be in accordance with BGL. All safety precautions & standards as prescribed by BGL are to be followed by members of bidder at the time of execution. This includes taking of necessary permits from respective BGL control room, its resubmission after completion of work and using personal protective equipment's.
7. The cascades are installed with top roof and other accessories, removal of these from cascade and their reinstalling after cascade testing is in bidder's scope. Damage of items during work will require their replacement by bidder on free of cost basis.

Signature & Seal of the Bidder

Page 4 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

8. The transportation of cascades from BGL station to bidder's workplace is in bidder's scope.
9. The Bidder shall carry out ultrasonic Flaw detection testing of cylinders as per IS 8451: 2009 amendment no 1st May 2013 and as per ASME Sec VIII Div 1 & ASME Sec V.
10. Bidder shall ensure all the cylinders are empty before dismantling. Bidder shall dismantle the cylinders, manifold tubing and fittings from the existing frame and has to note down all the cylinder numbers for each specific cascade. Remove the cylinder valve by using proper tools (Do not use adjustable spanner) Plug the cylinder to avoid any dust particle entering inside cylinder.
11. The bidder shall carry out cascade hydro-stretch testing, as per the gas cylinder rule 2004 and subsequent amendment. Hydro-stretch testing job has to be completed as per IS 5844 with future amendment.
12. The Bidder must have all the required instruments, i.e. high pressure pump, drying unit, ultrasonic thickness measuring instruments, oxygen analyzer & other required instruments to carry out the jobs. **The bidder shall submit list of such tools as part of bid.**
13. The normal operating pressure of CNG cylinders is 255kgf/cm² and testing is 435 kgf/cm². The bidder shall check same from cylinder and carry out testing accordingly.
14. Bidder shall calibrate SRV, PG's, TG's of the cascades as per the standards with Master traceable to National or International standards and submit the calibration certificate along with master calibration certificates of master calibrating instruments.
15. The Bidder shall repair cascade frame as per the requirement. Payment for the repair work will be made as per the SOR. The cascade repair will include repair / replacement of structure.
16. The bidder shall arrange for replacement of defective tubing and fitting as per requirement of the job. BGL may provide tubing and fittings on request if available with us for Part - II.
17. The bidder must have trained workforce to do the SS double ferrule connections, joints etc. The training has to be imparted by M/s Swagelok or M/s Parker Hannifin, Mumbai.
18. The Bidder shall paint the cylinders after priming and surface preparation by sand blasting/automatic wire brushing as per the industry practice. The Bidder shall also paint the structure of cascade as per the industry painting standards. The paint done on cylinder and structure should be of good quality and fit for 3 years period. Any defect in painting will be repaired by bidder on free of cost basis else will lead to penalty. Any cost associated with rework of painting viz transportation, dismantling & assembling of cascade etc will be in bidder's scope and BGL will not pay any amount against this. Delay in completion of testing work will lead to penalty as per the penalty clause.
19. The Bidder shall reassemble cascade (CNG Cylinders, PRDs, Valves, SS Tubing, Frame, Manifold etc.) as per the original configuration of the cylinders. The bidder shall provide and

Signature & Seal of the Bidder

Page 5 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

replace packing of cascade for ensuring no metal to metal contact between cylinder and cascade structure. Bidder should replace defective parts with new ones. Providing of new packing material, cylinder clamps, studs, gland nuts, Teflon washer for gland nuts etc., for replacement of old parts shall be in bidder scope. The bidder shall use spring washers for clamping of cylinder on structure. However payment for spares & services as mentioned in SOR PART-II shall on actual basis and submission of material reconciliation and handing over of removed defective spares/ parts to BGL for each cascade.

20. The bidder shall replace defective cylinder valves after confirmation by BGL. Payment for replacement of valves will be made as per the SOR. The valve used for the purpose shall be as per the IS 3224 and shall meet all necessary statutory requirements including approval from BGL.
21. The bidder shall replace Pressure Rupture Discs(PRD)s/Burst Discs along with fusible plug as per the instructions of BGL. The bidder shall arrange for replacement of these in cascades. The bidder shall prepare reconciliation statement and shall return used spares to BGL.
22. The joint inspection to be done to assess the spares consumption for other than consumables like ferrules etc prior to the dispatch of the each cascade for execution at site.
23. The bidder shall transport the cascade back to the any CNG station in Vijayawada and Kakinada GAs as per instruction of EIC. The reinstallation work shall have to be necessarily carried out in daytime. Required services viz tempo, crane, rigger etc. will be in bidders scope.
24. Deviation in the clause no 23 mentioned above will be considered as defect in service and will lead to penalty. Also, the bidder shall have to rectify the same at its cost and risk.
25. The bidder shall ensure proper anchoring of the cascade on the base and shall connect earthing strip with the cascade. The bidder shall also carry out necessary tubing to connect the cascade with station.
26. After connection of the tubing, performance / leak testing of the cascades is to be carried out at full pressure for 4 Hrs, by the Bidder's personnel in presence of BGL Engineer / Technician. Any repairing / replacement required at the time of testing, have to be carried out by the Bidder, free of cost. At installation locations, leak checks to be carried out.
27. Testing Certificates, as per Gas Cylinder Rules 2004, for each cylinder shall be submitted within 7 days of testing & erection. The certificates shall be given in one set as original & one set in pdf format in CD/DVD along with all test results .
28. The bidder shall test cascade tubing with pressure for leakage in its workshop.
29. The bidder to ensure strict adherence of BGL schedule for cascade lifting from station, cascade testing , cascade unloading in station, cascade testing in station, defect repair etc. Deviation in date of lifting of cascade from schedule will be treated as defect in service and penalty will be levied on the bidder.

Signature & Seal of the Bidder

Page 6 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

30. All the cascades of BGL are to be tested as per the statutory requirement and any selective testing of cascade will not be accepted and will lead to penalty.
31. Cascade requiring shifting, installation and commissioning for reasons other than cascade hydro testing are also covered in scope of contract. A separate item for loading, unloading, transportation & commissioning of cascade is mentioned in SOR and will be applicable for such shifting work.
32. Rejected Cylinder shall be handled according to Gas Cylinder rules and CCOE Regulation from time to time. Rejected Cylinders should be handed over to BGL

Other Terms & Conditions:

1. The Bidder shall ensure strict adherence of all safety rules and regulations of BGL.
2. The Bidder must have valid authorization for testing of CNG cylinders from Chief Controller of Explosives, Nagpur or respective PESO officials. A copy of the valid authorization has to be submitted along with the offer. The authorization should be valid throughout the tenure of the contract. **Offers without the copy of valid authorization from CCOE shall be rejected.**
3. BGL reserves the right to check the certificate at any time during the contract period.
4. BGL Engineers will inspect testing at Bidder's site on regular basis. BGL may ask for dispatch of cascade after verification of BGL engineer.
5. 2-way valves, 3-way valves & Pressure Gauges, if required to be replaced, shall be provided by BGL.
6. Appropriate marking showing date of testing shall be provided on each cylinder, as per Gas Cylinder Rules, 2004 and as per applicable recent amendments.
7. The bidder shall fix a plate on cascade with all necessary details including testing date, Due date, testing agency, cascade manufacturing year, cylinder serial numbers included etc. following the guidelines of PESO. The information plate shall be approved by BGL prior to fixing.
8. The bidder shall submit certificate in hard as well as in soft format as pdf file along with all test results.
9. The Bidder shall have a valid E Mail ID for day to day communication.
10. The Bidder is required to carry out all services as mentioned in the Scope of Services and Schedule of Rates on all the 365 days including Sundays and all Holidays.
11. The Bidder shall allow weekly rest to his workmen and daily working hours will be fixed as per the relevant Act/Law/and Rule made there under. However, no work shall be left

Signature & Seal of the Bidder

Page 7 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

incomplete/unattended on any holiday/weekly rest. The Bidder or his authorized representative shall interact with Engineer-in-charge on regular basis.

12. The Bidder shall provide all statutory /legal facilities to its workmen/employee as per the relevant Act/Law/and Rule including applicable rules and laws of the state.
13. The Bidder agrees to indemnify BGL directly or indirectly any loss or injury caused to BGL employee/agent/customer/public due to careless, negligent, inexperienced act or default of the Bidder, his/her agents, representatives or employees. BGL shall be the sole judge as regards the quantum of loss or damage and it shall be entitled to deduct from the amounts payable hereunder to the bidder, the cost of repairs or the amount of loss or damages.
14. Regarding work completion, the decision of the Engineer-in-Charge will be final and binding.
15. All personnel of the Bidder entering on work premises shall be properly and neatly dressed and shall wear cotton uniform, safety shoes, badges, (identity card) while working on premises of the company including work sites.
16. Bidder shall maintain all statutory records like attendance register, wage register, copies of PF &ESI return etc. Bidder shall submit records to BGL for verification along with the invoices.
17. The Bidder's representative/supervisor shall report daily to the Shift-in-Charge in the control rooms for day-to-day working, during execution of work at BGL sites.
18. The Bidder will strictly adhere to all the safety rules and regulations prevailing and applicable from time to time at the installations as directed by BGL.
19. The rates quoted /agreed by the bidder are inclusive of all the taxes, duties.
20. It will be the responsibility of the bidder to pay as per the minimum wages of the appropriate government rules applicable under the Minimum Wage Act. Bidder shall submit records to BGL for verification along with the invoices.
21. The Bidders shall provide proof in respect of separate PF Code/No of the concerned RPF Commissioner / Authority.
22. Vendor has to consider, within this scope any additional test or requirements, arising out of any revision in statutory notification related to gas cylinder rules.
23. Quantities of cascade as per SOR are tentative and may change as per actual requirement. BGL does not guarantee for quantity of work awarded.

Signature & Seal of the Bidder

Page 8 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

COMPLIANCE CLAUSE:

Bidder undertakes to comply with all laws/rules/regulations applicable to his business and on enquiry of the same shall furnish information/documents to BGL within 7 days for such enquiry with BGL.

SCOPE OF WORK AT PESO / CCOE APPROVED WORK PREMISES

1. Contractor shall carry out testing of CNG cascade cylinders at PESO approved testing facility as per Standard IS 5844, IS 8451 (Latest Amendments) and Gas Cylinder Rules 2004 and latest amendments.
2. **Contractor shall carry out following activities at his works:**
 - 2.1 Unloading of CNG cascade by suitable capacity crane/hydra and bidder should ensure the fitness of lifting machine at his risk.
 - 2.2 Dismantling all fittings, tubes and cylinders.
 - 2.3 Opening valves and De-gassing the cylinders by Nitrogen gas.
 - 2.4 Cleaning the cylinders from inside with wire brush.
 - 2.5 Weighing the cylinder.
 - 2.6 External inspection (thickness, bulge, burn, dents, dig etc.).
 - 2.7 Wall thickness measurement with ultrasonic.
 - 2.8 Internal inspection thickness test including Boroscopy and External inspection thickness test including Ultrasonic.
 - 2.9 Hydrostatic stretch test as per IS 5844 and Gas Cylinder Rules – 2004 and latest amendments in Jacketed method.
 - 2.10 Steam and vacuum cleaning of cylinders.
 - 2.11 Drying of Cylinders from inside by Hot air.
 - 2.12 External sand blasting of cylinders and frame structures.
 - 2.13 Ultrasonic Flaw detection test
 - 2.14 Fixing of valves, pneumatic testing.
 - 2.15 De-shaping of unserviceable cylinders.
 - 2.16 Cascade painting and marking as per IS 5844, Gas Cylinder Rules 2004.
 - 2.17 Check the good working condition of valve, threading, burst disc, tubing's and fittings.
 - 2.18 After testing of cylinders, contractor shall carry out loading and fixing of cylinders on cascade frame.
 - 2.19 Contractor shall carry out refitting and assembling tubes, valves and fittings etc.
 - 2.20 Bidder shall fix a plate on cascade with all necessary details including test date, due date, testing agency, cascade manufacturing year, cylinder serial numbers etc. The information plate shall be approved by BGL prior to fixing
 - 2.21 Testing of CNG Cylinder Valves Should be carried out by Hydraulic Pressure at 300 Bar.
 - 2.22 To replace all Rupture Burst Disc of CNG Cascade Cylinders as mentioned in SOR



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

SECTION 8:

SPECIFICATION OF WORK



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

SPECIFICATION OF WORK:

Work shall be carried out as per following safe engineering practices.

1. Degassing.
2. Internal and External examination.
3. Record of test.
4. Marking.
5. Painting.
6. Calculation sheet.
7. History card.
8. Related instrument calibration.
9. Explosive meter check up.
10. Cylinder weight check up.
11. Final inspection.

1. Re-Testing of cylinder:

- 1.1 Shot blasting of cylinder after Hydro- Testing.
- 1.2 Cleaning of cylinders.
- 1.3 Ultrasonic Flaw detection testing of cylinders on parallel portion of the cylinders.
- 1.4 Hydro static stretch testing of cylinders as per Gas Cylinder Rules 2004 and IS 5844 and latest amendments. In Jacketed method.
- 1.5 Issuing test certificates.

2. CNG cylinder valves:

- 2.1 Cleaning and overhauling of complete valves (Teflon packing, gland nut, spindle seat, retainer plate etc.
- 2.2 Burst disc, needle valve checking & replacement if required by BGL.
- 2.3 Testing of all valves for leak/passing by purging Nitrogen up to 150 bar.

3. Cylinder clamps:

- 3.1 Remove the clamps from cascade.
- 3.2 Replace the old studs with the new studs.
- 3.3 Zinc plating the complete clamps
- 3.4 Refix the clamps by using new lock nuts.

4. Cascade Tubing's:

- 4.1 Dismantling the complete SS tubing's.
- 4.2 Checking of all nut & ferrule & cleaning and replacement if required by BGL.
- 4.3 Replacement of Knobs of all valves if required by BGL.
- 4.4 Re fixing of tubing, if required replace tubing.
- 4.5 Hydro testing of tubing at 300 bars.
- 4.6 Flushing of complete tubing by using Nitrogen.
- 4.7 The SS Tubing, Fittings should be tested by Pneumatic Pressure for leakages at 300 bars. & Pressure testing, leak checking of cascades tubing's, fittings with air/Nitrogen at 255 Kg/cm².
- 4.8 Calibration of SRVs and Pressure Gauges with repairing & replacement with new may be done if found beyond repair.

Signature & Seal of the Bidder

Page 11 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

5. Painting of Cascade Frame & Cylinder :

- 5.1 Checking of cascade frame for any damage or corrosion.
- 5.2 Repairing the damage parts, includes cutting of steel frame and welding, and providing minor steel sections.
- 5.3 Sand blasting of complete frame including Angles, Brackets & Channels.
- 5.4 Re-fixing the Angles & Channels by using new Nut Bolts
- 5.5 Painting(Cascade Frame): Painting of Cascade Frame , Cylinders shall comply minimum Coating Thickness as per latest applicable standards Primer Coat: 2 coat of Zinc phosphate primer-coating thickness minimum 35 microns(μ) each coat.
Finish Coat: Two coat of Epoxy golden yellow (shade no: 356)-coating thickness minimum 35 microns(μ) each coat.
Total Coating (Primer & finish) Thickness minimum 140 microns (μ)
- 5.6 Painting(Cylinder: As per IS 4379): Primer Coat: One coat of Epoxy grey primer -coating thickness 25-30 microns(μ) Finish Coat: One coat of Epoxy White shade on Cylinder shell at neck end of cylinder: coating Thickness 40-50 microns (μ) (Shade – RAL No 9003)
Total Coating(primer & finish) thickness 65-80 microns(μ)

6. Cascade Assembly testing & Inspection

- 6.1 Each cascade assembly with all tubing fittings and valves shall be pressure tested with Nitrogen at desired pressure not less than 250 bar to ensure no leakages prior to dispatch
- 6.2 After completion of testing process, Cascade should be hand overed to BGL with a positive pressure of Nitrogen at 5 bar before dispatch. Ensure purity of Nitrogen >98%.

7. Loading & Unloading of CNG Cascade Cylinder:

- 7.1 Loading/Unloading of CNG Cascade Cylinder shall be carried out either by Hydra or Mobile crane, depending of the requirement of specific job. Any other lifting equipment identified on case basis shall also be included as part of this Contractor's scope.
- 7.2 Mobile crane with Telescopic boom of required capacity shall be used. The capacity of crane shall be calculated by the Contractor prior to start of job keeping in view the load to be lifted and the distance/angle of lift and loading.
- 7.3 Loading & Un-loading of CNG Cascade Cylinders shall be from BGL's Location and Retail Outlets where CNG Cascade Cylinders are mounted on the Compressors



Bhagyanagar Gas Ltd.

**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

**SECTION – 9
SPECIAL CONDITIONS OF
CONTRACT**



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

GENERAL INFORMATION: -

The special conditions of contract shall be read in conjunction with general condition of contract (GCC), Schedule of rates, scope of work and any other document forming part of contract, wherever Context so Requires. GCC is available at tender issuing office and same shall be referred by Bidder. Notwithstanding, the subdivisions of the documents into separate sections every part of each shall be deemed to be supplementary of every other part and shall be read with and into the Contract so far as it may be practicable to do so. Where any portion of the special conditions of the Contract (SCC) is repugnant to or at variance with any provisions of the GCC then provision of SCC Shall be deemed to override the provision of GCC only to the extent of each repugnance or variations. In case of any contradictions the Decision of the Engineer-In-Charge will be final and binding on the Contractor.

In case of an irreconcilable conflict between Indian or other applicable standards, General Conditions of Contract, Special Conditions of Contract, Specification, Drawings or Schedule of Rates, the following shall prevail to the extent of such irreconcilable conflict in order of precedence:

- i. Letter of Acceptance/ LOI along with Statement of Agreed Variations.
- ii. Schedule of Rates as enclosures to Letter of Acceptance
- iii. Special Conditions of Contract
- iv. Service descriptions
- v. Instruction to Bidder
- vi. General Conditions of Contract
- vii. Indian Standards
- viii. Other applicable standards

1. Price basis:

Bidders to quote on the basis of door deliver inclusive of all taxes and duties, loading & unloading and installation charges as per scope of work defined in this tender. No additional payment shall be admissible over and above the quoted price.

2. Validity of quoted rates:

The rates quoted and accepted shall remain valid for the entire period of contract of three yeys and no escalation whatsoever permissible after the award of contract.

The contract may be extended for a maximum period of 1 year at the same rates, terms and conditions subject to satisfactory performance of vendor and discretion of BGL, after the completion of contract period.

3. Taxes and duties:

The entire work covered under this contract shall be treated as works contract services. Bidder shall be required to quote their rates for all the SOR items inclusive of all applicable taxes as defined in the tender document. The rates are inclusive of all applicable taxes in contract value. Any statutory variation in the Goods & service tax during the scheduled completion period only shall be considered by the owner against documentary evidence.

4. Payment Terms:

- i. 100% payment within 30 days after submission of invoice along with Test Certificates / Reports certified by Engineer-In-Charge of BGL. Contractor has to submit the invoice against each cascade.
- ii. Payment for spares shall be done on actual utilization certified by Engineer-In- Charge.

Signature & Seal of the Bidder

Page 14 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

5. Work order / Contract validity period:

36 months from the date of LOI/ WO. Bidder should immediately mobilize the works as from the date of Intimation of EIC through email/letter.

5.1) Individual Completion Period:

The bidder needs to lift each lot of cascades up to 03 nos. within 01 week from the date of intimation by EIC to be intimated through letter or email. Completion period of each lot of cascades up to 03 nos. shall be 30 days from the date of lifting of last cascade of each cascade lot. A lot of cascades consist up to 03 Cascades as decided by EIC. The bidder must lift each cascade before one month of the hydro test due date, as per the provided list in section 10.

6. Penalty/ PRS:

- a) Delay beyond 01 week from the date of intimation in lifting of last cascade of cascade lots up to 03 no's from BGL's station/ site shall incur a penalty up to Rs 2000/- per week per cascade.
- b) Delay beyond 30 days from the date of lifting of last cascade of cascade lots up to 3 no's in commissioning/ installation of tested/ certified cascade at BGL's station/ site after testing of cascade as per the scope of works of tender shall incur a penalty up to Rs 2000/- per week per cascade.
- c) Delay beyond 15 days from the date of intimation of defect in quality of work during next 2 months of operation from the date of commissioning of each respective cascade shall incur a penalty up to Rs 2000/- per cascade. The bidder shall have to arrange rectification of defect at no additional cost.

7. Transportation & Dispatch Basis:

Transportation (to & pro) shall be in the scope of contractor. The contractor should lift CNG Cascade from various sites of BGL up to its testing unit at its own cost & risk. Loading & Unloading charges shall on contractors scope. The contractor should deliver these CNG Cascade(s) to its respective place or as instructed by BGL at its own risk and cost.

If any damage occur during transportation and or mishandling during testing processes, the full rectification cost shall be assessed by BGL and shall be deducted from Bill(s). If the damage found non repairable then that should be provided by the contractor.

a. Transit Insurance

Transit insurance has to be arranged by Contractor and charges are to be included in SOR.

8. Contract Performance Security / Contract Performance Bank Guarantee:

- i. The Contractor shall furnish to the Employer, within 30 days from the date of notification (FOA/ LOI/ LOA/WO) of award, a security of 5% of one year contract value within 30 days of award of FOA/WO/PO or 2.5% of contract /order value within 30 days of award and balance to be deducted in each RA bills till balance 2.5% amount is achieved. The deducted amount can be released/ deduction can be stopped against submission of Bank Guarantee of equivalent amount.
- ii. For security deposit/ Contract Performance Guarantee purpose, Contract/ Order Value as mentioned above shall be exclusive of taxes and duties.



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

- iii. The Contract Performance Guarantee will be obtained for a period of 90 days beyond the contract period/ duration and applicable Warranty/ Guarantee /Defect Liability Period (if any).
- iv. Contract performance guarantee is to be submitted by bidder within 30 days after issuance of Fax/Letter of Intent /Acceptance (notification of Award) and in event of delay in submission of CPBG / SD, the contract can be terminated.
- v. In the event of Completion of project being delayed beyond the Scheduled Completion Date, for any reason whatsoever, the Owner may without prejudice to any other right or remedy available to the Owner, operate the Bank Guarantee to recover the Compensation for delay leviable as per relevant clause of GCC. The Bank Guarantee amount shall thereupon be increased to the original amount, or the ASSOCIATES may alternatively submit a fresh Bank Guarantee for the equivalent amount of compensation for delay recovered.

The Contract Performance Bank Guarantee will initially be kept valid for 90 days beyond the validity of contract and will be discharged not later than three months from the date of expiration of contract and Contractor's entire obligations including warranty obligations under the contract. Remaining **GCC clause 2.13 of Contract Performance Security shall be followed.**

9. Defect Liability Period (DLP):

03 months from the date of completion of Work Order.

10. Retesting Certification issued by PESO/CCOE for carrying out the hydro test of CNG Cascade Cylinders at his premises, according to IS:5846-1993, IS :8451-2009, IS:5844-1970 and gas Cylinder rules-2004 should remain valid throughout the period of Work Order.

11. Bidders to submit documentary evidences of available machineries for carrying of retesting of Cylinders along with the Bid.

12. In case of any change in location for transportation of hydro tested cascade (i.e. Dispatching Cascade received from one GA to another GA), Vendor may note that, the transportation charges shall be payable @ 50% per cascade as applicable for received cascade. Similarly, @ 50% per cascade will be payable as applicable in the other GA work order rates for the dispatched location.



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

**SECTION – 10
LOCATION OF CYLINDER
CASCADES**



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

Description and Location of Cascades due for Hydro testing:

Sr. No	Make	Cascade No.	Location	No. of Cylinders	Hydro Test Due Date
1	EKCT	EKCT/BGL/260-40/10	Vijayawada	40	23-12-2024
2	RCPL	RCPL/BGL-40/255-05	Vijayawada	40	11-01-2025
3	BPC	BPC/BGL-40/255/163	Vijayawada	40	01-02-2025
4	RCPL	RCPL/BGL-40/255-11	Vijayawada	40	13-02-2025
5	BPC	BPC/BGL-40/255-168	Vijayawada	40	03-03-2025
6	BPC	BPC/BGL-40/255-174	Vijayawada	40	04-03-2025
7	EKCT	EKCT/BGL/260-S-40/14	Vijayawada	40	15-03-2025
8	EKCT	EKCT/BGL/260-40/18	Vijayawada	40	05-04-2025
9	EKCT	EKCT/BGL-30/255-09M	Vijayawada	30	12-04-2025
10	BPC	BPC/BGL-40/255-170	Vijayawada	40	17-04-2025
11	EKCT	EKCT/BGL-30/255-06M	Vijayawada	30	22-04-2025
12	BPC	BPC/BGL-40/255-171	Vijayawada	40	24-04-2025
13	MKC	MKC/BGL/3000/11/0018	Vijayawada	40	05-05-2025
14	EKCT	EKCT/BGL/260-40/25	Vijayawada	40	09-05-2025
15	EKCT	EKCT/BGL/260-40/22	Vijayawada	40	13-05-2025
16	RCPL	RCPL/BGL-S-40/255-K-09	Vijayawada	40	10-06-2025
17	MKC	MKC/BGL/3000/11/002	Vijayawada	40	20-06-2025
18	MKC	MKC/BGL/3000/11/0014	Vijayawada	40	19-07-2025
19	MKC	MKC/BGL/3000/12/0023	Vijayawada	40	03-11-2025
20	EKCT	EKCT/BGL/260-S-40/26	Vijayawada	40	10-11-2025
21	RCPL	RCPL/BGL-40/255-06	Vijayawada	40	10-12-2025
22	RCPL	RCPL/BGL-M-40/255-37	Vijayawada	40	13-12-2025
23	MKC	MKC/BGL/3000/11/0007	Vijayawada	40	17-12-2025
24	MKC	MKC/BGL/3000/11/0010	Vijayawada	40	20-12-2025
25	RCPL	RCPL/BGL-S-60/255-05	Vijayawada	60	23-01-2026
26	RCPL	RCPL/BGL/-M-40/255-41	Vijayawada	40	11-02-2026
27	RCPL	RCPL/BGL-S-40/255-50	Vijayawada	40	20-02-2026
28	RCPL	RCPL/BGL-S-40/255-54	Vijayawada	40	31-03-2026
29	RCPL	RCPL/BGL-S-40/255-55	Vijayawada	40	06-04-2026
30	RCPL	RCPL/BGL-S-40/255-56	Vijayawada	40	30-01-2027
31	MKC	MKC/BGL/3000/11/0013	Vijayawada	40	30-12-2027
32	RCPL	RCPL/BGL-S-60/255-12	Vijayawada	60	30-12-2027
33	EKCT	EKCT/BGL-40/255-14	Vijayawada	40	31-01-2028
34	EKCT	EKCG/BGL-40/255-07	Vijayawada	40	13-03-2028
35	RCPL	RCPL/BGL-40/255-04	Vijayawada	40	30-03-2028
36	EKCT	EKCT/BGL/260-40/17	Vijayawada	40	04-07-2028
Total Cylinders			1460		

Signature & Seal of the Bidder

Page 18 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

S.NO	Make	Cascade No	Location	No. of Cylinders	Hydro Test due date
1	EKCT	EKCT/BGL-40/255-11	Kakinada	40	23-02-2025
2	EKCT	EKCT/BGL-S-40/260-04	Kakinada	40	24-07-2025
3	EKCT	EKCT/BGL/260-S-40/28	Kakinada	40	14-08-2025
4	EKCT	EKCT/BGL-40(S)/260-06	Kakinada	40	29-10-2025
5	RCPL	RCPL/BGL-M-40/255-36	Kakinada	40	22-12-2025
6	RCPL	RCPL/BGL-M-40/255-42	Kakinada	40	28-01-2026
7	RCPL	RCPL/BGL-S-40/255-51	Kakinada	40	17-04-2026
8	RCPL	RCPL/BGL-M-40/255-43	Kakinada	40	28-04-2026
9	EKCT	EKCT/BGL-40/260-08	Kakinada	40	01-06-2026
10	RCPL	RCPL/BGL-S-40/255-52	Kakinada	40	28-06-2026
11	RCPL	RCPL/BGL-S-40/255-66	Kakinada	40	13-07-2026
12	RCPL	RCPL/BGL-S-40/255-67	Kakinada	40	31-07-2026
13	RCPL	RCPL/BGL-S-60/255-10	Kakinada	60	22-11-2026
14	RCPL	RCPL/BGL-S-60/255-04	Kakinada	60	04-12-2026
15	EKCT	EKCT/BGL-40/255-13	Kakinada	40	01-12-2027
16	RCPL	RCPL/BGL-40/255-16	Kakinada	40	12-03-2028
Total Cylinders			680		
Total Cylinders VJA & KKD			2140		

Note: Serial Numbers and make of CNG storage cylinders may change as per actual site location.

a) Location indicates CNG stations in various locations in Vijayawada & Kakinada GA. Bidder should lift the cascade from the CNG station / location as specified by BGL.



Bhagyanagar Gas Ltd.

**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

**SECTION – 11
SCHEDULE OF RATES (SOR)**



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

BHAGYANAGAR GAS LIMITED

SCHEDULE OF RATES

**Annual Rate Contract for Inspection, Testing, and Refurbishment of CNG Cascades at Vijayawada and Kakinada for a Period of Three
Years**

Name of Bidder

Part-I

Sr. No .	Description	UO M	Qty (Total No. of Cascade Cylinders)	Unit Rate (Rs.) per Cylinder inclusive of all taxes & duties but exclusive of GST	Sub Total	GST%	GST Amount (Rs.)	Total Amount (Rs.) inclusive of all taxes & duties and GST
-------------------------	--------------------	-----------------	--	--	------------------	-------------	---------------------------------	---



Bhagyanagar Gas Ltd.

**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

1	Re-furnishment, testing and Certification of CNG Cascade cylinders including mandatory hydrotesting of 75 WL capacity of CNG cylinders as per IS-5844 and Gas cylinder Rules 2010; Ultrasonic Flaw Detection Test on parallel portion of CNG cylinders including dismantling and refitting at BGL's site, pneumatic testing at site, re-commissioning, etc. as per scope of work as mentioned in the tender for the period of 3 years as per PESO norms, Gas Cylinder rules 2010 & other applicable standards (latest standards). Faulty Spares shall be provided & replaced by the vendor as per the annexure (Total- 52 nos. cascades of 30/ 40/60 cylinders in each cascade)	Nos	2140		0		0	0
Sr. No .	Description	UO M	Qty (Total No. Of Cascades)	Unit Rate (Rs.) per Cascade inclusive of all taxes & duties but exclusive of GST	Sub Total	GST%	GST Amount (Rs.)	Total Amount (Rs.) inclusive of all taxes & duties and GST

Signature & Seal of the Bidder



Bhagyanagar Gas Ltd.

**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

2	Transportation of Cascades from BGL's site to work premises and work premises to BGL's site in Vijayawada, loading / unloading at both places, dismantling and refitting at BGL's site, pneumatic testing at site, recommissioning(including transit insurance) including Temporary replacement of cascade provided by BGL for continuing the operation at BGL site, (however spare cascade) shall be provided by BGL Qty- (Total No. Of Cascades)	Nos	36		0		0	0
3	Transportation of Cascades from BGL's site to work premises and work premises to BGL's site in Kakinada, loading / unloading at both places, dismantling and refitting at BGL's site, pneumatic testing at site, recommissioning(including transit insurance) including Temporary replacement of cascade provided by BGL for continuing the operation at BGL site, (however spare cascade) shall be provided by BGL Qty- (Total No. Of Cascades)	Nos	16		0		0	0
Total Amount in Rs inclusive of all taxes & duties and GST for Part I								0

Signature & Seal of the Bidder



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

SCHEDULE OF RATES

Part - II: Spares

S.No	Description	UOM	Qty	Unit Rate (Rs.) inclusive of all taxes & duties but exclusive of GST	Sub Total	GST%	GST Amount (Rs.)	Total Amount (Rs.) inclusive of all taxes & duties and GST
1	Cylinder Valve -vanaz make	No.	2		0		0	0
2	Burst Disc / Pressure Rupter disc (PRD), Vanaz make	No.	40		0		0	0
3	3/4 " OD SS Tube, Sandivik make	Meter	20		0		0	0
4	1/4 " OD SS Tube, Sandvik make	Meter	10		0		0	0
5	SRV size:1/4" Swagelok/parker make	No.	2		0		0	0
6	Cylinder valve Knob, vanaz make	No.	4		0		0	0
7	Union Cross 3/4", Swagelok/parker make	No.	4		0		0	0
8	Union Tee 3/4", Swagelok/parker make	No.	2		0		0	0
9	Check Valve 3/4"OD, Swagelok/parker make	No.	2		0		0	0
10	Male Connector 3/4"OD - 1/4" NPT(M) Swagelok/parker make	No.	20		0		0	0
11	2-Way valve Manifold block, Swagelok/parker make	Set	2		0		0	0

Signature & Seal of the Bidder



Bhagyanagar Gas Ltd.

**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

12	3/4" OD 2-way Valve Panel Mount, Swagelok/parker make	Set	2		0		0	0
13	Male Connector (1/4" OD Tube x1/4" NPT Male)	No.	4		0		0	0
14	Female Bulkhead Connector (1/4" OD Tube x 1/4" NPT-F)	No.	4		0		0	0
15	4" Dial Glycerine filled Pressure Gauge (Range 0 to 420 kgf/cm2 with 1/4" NPT-M Bottom end connection)	No.	10		0		0	0
16	3/4" x 3/8" NPT Male Connector, Swagelok/parker make	No.	4		0		0	0
17	3/8" elbow SS 316, Swagelok/parker make	No.	2		0		0	0
18	3/8" X 1/4" NPT Male Connector, Swagelok/parker make	No.	20		0		0	0
19	1/4" Union SS 316, Swagelok/parker make	No.	4		0		0	0
20	3/4" Union SS 316, Swagelok/parker make	No.	4		0		0	0
21	2 WAY Valve knob	No.	4		0		0	0
22	Reducer 3/4"Od*1/4, Swagelok/parker make	No.	4		0		0	0
23	1/4" OD 1/4" NPTM, Male Connector, Swagelok/parker make	No.	4		0		0	0
24	Fabrication Installation of Gauge Panel	No.	4		0		0	0
25	Supply & installation of canopy for cascades	Sq. m	52		0		0	0
26	Repair of cascade frame structure including welding, supply & installation of structural material, equipment and manpower etc., if required	Rm	10		0		0	0

Signature & Seal of the Bidder

Page 25 of 26



**Annual Rate Contract for Inspection, Testing, and
Refurbishment of CNG Cascades at Vijayawada and Kakinada
for a Period of Three Years
Bid Document No. BGL/689/2025-26**

Vol II of
II

27	Removal & Re-installation of MS weld mesh fencing used for barricading of CNG unit area to facilitate removal and re-installation of cascade mounted on cascade structure /ground. Rate to include breaking of RCC/WBM/Paver blocks, dismantling of welded joints/MS & re-welding/fabrication etc. grounding it to existing position as per direction of EIC	Rm	4		0		0	0
Total Amount in Rs inclusive of all taxes & duties and GST for Part-II								0
Total Amount in Rs inclusive of all taxes & duties and GST (I+II)								0

Signature & Seal of the Bidder